

## SAND SILOS – PAESEN CONCRETE FACTORY – BELGIUM

Sand silos at the **PAESEN** concrete factor April 2006.

The silos were sandblasted and coated with **ZINGA** and topcoated with 2c Pu Primer Finish with a mist and full coat technique by the Construction and Application company **ELLIMETAL** in Meeuwen.



### System:

ZINGA 1 x 80 µm DFT  
2c Pu Primer Finish 1 x 70 µm DFT  
mist coat/full coat

